

March 2, 2022

BID DATE: March 22, 2022

BID TIME: 2:00:00 pm

ADDENDUM #1

To the PLANS and SPECIFICATIONS
for the

Sylvan Union School District

Standiford Elementary School Pavement Replacement Project & Site Improvements

BID #2021-22 #10

GENERAL

The following addendum to the Plans and Specifications shall take precedence over and be amended to the original Plans and Specifications.

ITEM #0.1: Field Office: A field office/trailer shall not be required as part of this project. The Contractor may provide a trailer or field office for their own use. The District will make space available for the construction progress meetings. Contractor shall provide temporary, portable restrooms at the site for contractor use.

ITEM #0.2: Contractor Prequalification: Contractor Prequalification will be received until **March 8, 2022, at 5:00pm**. Prequalification Questionnaires are available on the District's Purchasing Website. Please direct all questions to Carol Smith at 209-574-5000 ext. 3200 or via email at: csmith@sylvan.k12.ca.us See bid docs for additional information.

ITEM #0.3: Bid Date: Sealed Bids (base bids) will be received until **2:00:00 p.m., March 22, 2022, at the District Office, Front Desk, 605 Sylvan Avenue, Modesto California**, at or after which time **all bids** will be opened and publicly read aloud. Any bid that is submitted after this time shall be non-responsive and returned to the bidder. Any claim by a bidder of error in its bid must be made in compliance with section 5100 et seq. of the Public Contract Code.

ITEM #0.3: Clarification, Striping: The Contractor shall take pictures of all existing striping prior to demolition and shall be responsible for recreating all existing striping, including colored striping / graphics.

ITEM #0.4: Clarification, Staking: The Contractor shall include construction staking in their bid.

CIVIL:

ITEM #1.0: Sheet C3.0 – Existing CMU Enclosure & Trash Enclosure: The existing concrete / paved surface at the interior of the existing CMU and trash enclosure is existing to remain.

ITEM #1.1: Sheet C4.0 – Proposed Keynote #1: Keynote #1 shall read: 6” concrete slab with #4 at 24” O.C ea. way, centered in slab, over 6” class 2 aggregate base over 6” of cement treated compacted subgrade (90%). All existing utility boxes, drain inlets, cleanouts, & manholes shall be adjusted to grade.

ITEM #1.2: Clarification, Sheet C4.0, Proposed Keynote #12: Sleepers shall be pressure treated 2x with width and length matching existing sizing, placed between ramp framing and pavement in existing positions.

LANDSCAPING:

ITEM #2.0: Clarification: Contractor shall be responsible for adjusting sprinklers & irrigation as required to accomplish the work and grade smooth all turf/landscape surfaces adjacent to any work performed.

SPECIAL NOTE:

It is the responsibility of each Bidder to acknowledge all addenda on the BID FORM.